



**ADDENDUM NO. 4
BID #25-1020
PROJECT MANUAL
FOR THE
BLACKBURN RESOURCE RECOVERY FACILITY
WASTE PROCESSING FACILITY PROJECT**

Signed, sealed, and dated this 7th day of August 2024

By: 
Bernie Garrett, P.E.



Title: Project Manager

Bidders on this Project are hereby notified that this Addendum shall be attached to and made a part of the above-named Bidding and Contract Documents dated May 2025.

The following items are issued to add to, modify, and clarify the Bidding and Contract Documents. These items shall have full force and effect as the Bidding and Contract Documents, and cost involved shall be included in the bid prices. Bids, to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

Acknowledge receipt of the Addendum by inserting its number and date on Page 2 of 4 of Section C-410 Bid Form. Failure to do so may subject the bidder to disqualification.

DRAWINGS

1. Delete the "Catawba Co Waste Processing Bid No. 25-1020_Addendum_2_Dwgs" found under link "Revised Civil Drawings" and dated Revision June 6, 2025. Replace with the "Bid No. 25-1020 08-05-2025-DEQ Approved Drawings."
2. Add Sheet 11 – NCDOT Driveway Encroachment Plan.
3. Add Sheet 12 – Post-Stabilization Fence Plan.

PROJECT MANUAL

1. Replace the Table 1 – Bid Form of Section C-410 with the Table 1 – Bid Form included in this addendum. Note that Item 41 – Check Dam has been added.
2. Replace Section 01025 – Measurement and Payment with the Section 10125 included in this addendum. Note that Item 1 – Mobilization has been revised and Item 41 – Check Dam has been added.

END OF ADDENDUM NO. 4

TABLE 1
Catawba County Waste Processing Facility Project
ADDENDUM 4
Bid Form

Item	Description	Quantity	Unit	Unit Price	Extended Total
1	Bonds, Mobilization and Insurance	1	LS		
2	Silt Fence	350	LF		
3	Construction Entrance	1	LS		
4	Skimmer Basin Outlet	1	LS		
5	Sediment Pond Riser Barrel	1	LS		
6	Porous Baffles	470	LF		
7	Grubbing/Stripping	6825	CY		
8	Excavation and Backfill	7200	CY		
9	Excavation and Stockpile	6600	CY		
10	Catch Basins	7	EA		
11	12-inch RCP	120	LF		
12	24-inch RCP	184	LF		
13	30-inch RCP	812	LF		
14	Asphalt Paving	1550	SY		
15	ABC Paving	10010	SY		
16	Sidewalk	100	SY		
17	Concrete Scale Ramps	4	EA		
18	Scale Foundation/Washout Slab	2	EA		
19	Scales	2	EA		
20	Stabilization	5.1	AC		
21	Bollards	12	EA		
22	Water Service	1	LS		
23	Sewer Service - Septic System	1	LS		
24	Chain Link Fence and Gates	3975	LF		
25	Pavement Striping	1	LS		
26	Concrete Walls/Foundations (Tire Pad)	1	LS		
27	Concrete Slab (Tire Pad)	1	LS		
28	PEMB Canopy	1	LS		
29	General Conditions-Building	1	LS		
30	Concrete	1	LS		
31	Masonry	1	LS		
32	Steel Carpentry	1	LS		
33	Moisture & Thermal Protection	1	LS		
34	Doors, Windows, & Glass	1	LS		
35	Finishes	1	LS		
36	Specialties	1	LS		
37	Plumbing	1	LS		
38	Mechanical	1	LS		
39	Electrical	1	LS		
40	Miscellaneous Work & Cleanup	1	LS		
41	Check Dam	5	EA		
TOTAL AMOUNT					

In words: _____

Bidder: _____

Date: _____

SECTION 01025

MEASUREMENT AND PAYMENT

PART 1: GENERAL

1.01 SCOPE OF WORK

- A The Project generally consists of furnishing and installing, complete, including labor, equipment, parts, materials, and other incidental work for the construction of the project as described in Section 01010 Summary of Work.
- B All contract prices included in Section C-410-Bid Form will be full compensation for all labor, materials, tools, equipment and incidentals necessary to complete the Work as shown on the Drawings and specified in the Contract Documents to be performed under this Contract.
- C The items listed below, refer to and are the same pay items listed in the Bid Form. They constitute all the pay items for the completion of the Work. No direct or separate payment will be made for providing miscellaneous temporary or accessory work, services, job signs, sanitary requirements, testing, safety devices, surveying, field engineering, approval and record drawings, water supplies, power, maintaining traffic, removal of waste, watchmen, and all other requirements of the General Conditions and DIVISION 1 - GENERAL REQUIREMENTS. Compensation for all such services, equipment and materials shall be included in the prices stipulated for the lump sum and unit price bid items listed herein.
- D Each lump sum and unit price will be deemed to include an amount considered by CONTRACTOR to be adequate to cover CONTRACTOR'S overhead and profit for each separately identified item.
- E Restoration is not a separate bid item but is considered to be an integral part of the work under the contract, and all contract bid prices include the cost of restoration necessitated by the work related to that bid item.
- F Progress Payment for any item for which certifying surveys are required by Section 01050 will be made based on estimated quantities verified by the ENGINEER. The ENGINEER will verify all final quantities prior to Final Payment for that item. Certifying surveys will be required for payment greater than 75% of the estimated total amount of that bid item as required by Section 01050. No Final Payment will be made for any item for which certifying surveys required by Section 01050 have not been submitted and approved by the ENGINEER.

1.02 BID ITEMS

Item 1: Bonds, Mobilization and Insurance

1. This Work shall consist of securing the appropriate bonds and insurance policies for the Project, and performance of preparatory construction operations, including the movement of personnel and equipment to the Project site, safety equipment and other facilities to begin work on a substantial phase of the Contract. Payment for this item will be made on a Lump Sum basis, wherein no measurement will be made. The Lump Sum price bid shall be full compensation for performing the specified work and the furnishing of all materials, labor, tools, equipment, and incidentals necessary to mobilize and subsequently demobilize. The amount of this item shall be limited to a maximum of five percent of the Line Items 2-41.

Item 2: Silt Fence

1. Measurement: The quantity of Silt Fence to be paid under this item will be the number of linear feet of Silt Fence complete and in place.
2. Payment: The unit price bid for this item will be full compensation for vegetation removal, furnishing, installing, inspection and maintaining Silt Fence as shown on the Drawings and specified herein, for the duration of the project or until areas are stabilized with vegetation. Silt Fence shall be removed upon completion and of the Project and successful stabilization of disturbed areas, as directed by the ENGINEER.

Item 3: Construction Entrance

1. The lump sum price for Construction Entrance shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Construction Entrance as shown in the Drawings and specified herein, including but not limited to, site preparations, geotextile fabric in areas subject to seepage or high water table, stone aggregate, maintenance and topdressing as required, and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 4: Skimmer Basin Outlet

1. The lump sum price bid for this item will be full compensation for all labor, materials, tools, equipment, supervision and incidentals required to construct the Skimmer Basin Outlet, including removal and disposal of existing structures, skimmer outlet, rip-rap dissipator, fittings, gaskets, emergency spillway, and other items required for the installation of the Skimmer Basin Outlet for which payment is not provided under other items in the bid form

Item 5: Sediment Pond Riser Barrel

1. The lump sum price bid for this item will be full compensation for all labor, materials, tools, equipment, supervision and incidentals required to construct the Sediment Riser Barrel, including removal and disposal of existing structures, precast concrete riser, filter diaphragm, skimmer outlet, anti-vortex device, barrel outlet pipe, rip-rap dissipator, flared end sections (FES), fittings, gaskets, emergency spillway, and other items required for the installation of the Sediment Basin Riser Barrel for which payment is not provided under other items in the bid form.

Item 6: Porous Baffles

1. Measurement: The quantity of Sediment Basin Porous Baffles to be paid under this item will be the number of linear feet of Sediment Basin Porous Baffles installed in accordance with the Plan Drawings.
2. Payment: The unit price bid for this item will be full compensation for furnishing and installing the Sediment Basin Porous Baffles as shown on the Drawings and specified herein and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 7: Grubbing/Stripping

1. Measurement: The quantity of Grubbing/Stripping which will be paid for under this item will be the actual number of cubic yards measured by comparing the pre-work topographic survey to the topographic survey performed after the grubbing/stripping and prior to excavation and backfill, as required in Section 01050.
2. Payment: The unit price bid for this item will be full compensation for excavation and stockpiling grubbing/stripping materials from within the limits grubbing/stripping as shown on the Drawings and specified herein. No Final Payment will be made for this line item for which certifying surveys required by Section 01050 have not been submitted and approved by the ENGINEER.

Item 8: Excavation & Backfill

1. Measurement: The quantity of Excavation & Backfill which will be paid for under this item will be the actual number of cubic yards measured by comparing the topographic survey performed after the stripping and grubbing and prior to excavation and backfill, to the topographic survey performed upon the completion of excavation and backfill, as required in Section 01050.

2. Payment: The unit price bid for this item will be full compensation for excavation and backfilling to the design Subgrade Plan as shown on the Drawings and specified herein including but not limited to hauling, and backfilling; compaction, quality control and surveying; drainage and dewatering; sheeting and bracing; test pits to verify location and depth of existing buried utilities and other facilities; care and protection of existing utilities and structures; site restoration; conformance to all federal, state, and county Standards and requirements; and all other work required or incidental to the satisfactory completion of all Work under this contract for which payment is not provided under other items in the bid form. No Final Payment will be made for any excavation and backfilling for which certifying surveys required by Section 01050 have not been submitted and approved by the ENGINEER.

Item 9: Excavation & Stockpile

1. Measurement: The quantity of Subgrade Excavation & Stockpile which will be paid for under this item will be the actual number of cubic yards measured by comparing the topographic survey performed after the stripping, clearing and grubbing and prior to excavation and backfill, to the topographic survey performed upon the completion of excavation and stockpiling, as required in Section 01050.
2. Payment: The unit price bid for this item will be full compensation for excavation and stockpiling to the design Subgrade Plan as shown on the Drawings and specified herein including but not limited to hauling, and stockpiling; compaction, quality control and surveying; drainage and dewatering; care and protection of existing utilities and structures; site restoration; conformance to all federal, state, and county Standards and requirements; and all other work required or incidental to the satisfactory completion of all Work under this contract for which payment is not provided under other items in the bid form. No Final Payment will be made for any excavation and stockpiling for which certifying surveys required by Section 01050 have not been submitted and approved by the ENGINEER.

Item 10: Catch Basins

1. Measurement: The quantity of Catch Basins to be paid under this line item is the actual quantity constructed in place, tested, and accepted by the ENGINEER.
2. The unit price for each Catch Basin shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Catch Basins as shown in the Drawings and specified herein, including but not limited to, excavation, dewatering, bedding material, backfill, testing, and all other work

required or incidental to the satisfactory completion of all work under this item.

Item 11: 12-inch RCP

1. Measurement: The quantity of 12-inch RCP to be paid for under this item will be the actual number of linear feet of pipe in place measured horizontally along the centerline of the installed pipes.
2. Payment: The unit price bids per linear foot for this items will be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the designated pipe as shown on the Drawings and specified herein, including but not limited to furnishing and installing all pipe, fittings, couplings, pipe bedding, pipe backfill, flared end sections, rip rap dissipators, cleaning, testing, certifying surveying, and all other appurtenances and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 12: 24-inch RCP

1. Measurement: The quantity of 24" Inlet Pipe w/ Flared End Sections to be paid for under these items will be the actual number of linear feet of pipe in place measured horizontally along the centerline of the installed pipes.
2. Payment: The unit price bids per linear foot for this items will be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the designated pipe as shown on the Drawings and specified herein, including but not limited to furnishing and installing all pipe, fittings, couplings, pipe bedding, pipe backfill, flared end sections, rip rap dissipators, cleaning, testing, certifying surveying, and all other appurtenances and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 13: 30-inch RCP

1. Measurement: The quantity of 30-inch RCP to be paid for under these items will be the actual number of linear feet of pipe in place measured horizontally along the centerline of the installed pipes.
2. Payment: The unit price bids per linear foot for this items will be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the designated pipe as shown on the Drawings and specified herein, including but not limited to furnishing and installing all pipe, fittings, couplings, pipe bedding, pipe backfill, flared end sections, rip rap dissipators, cleaning, testing, certifying surveying, and all other appurtenances and all other work

required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 14: Asphalt Paving

1. Measurement: The quantity of Asphalt Paving which will be paid for under this item will be the actual number of square yards of Asphalt Paving as measured in the two-dimensional plan view installed and minimum thickness as verified by the Road Thickness Survey as required by Section 01050 – Field Engineering.
2. Payment: The unit price bid for this item will be full compensation for all labor, materials, tools, equipment, supervision required to furnish and install the Asphalt Paving as shown on the drawings and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 15: ABC Paving

1. Measurement: The quantity of ABC Paving which will be paid for under this item will be the actual number of square yards of Asphalt Paving as measured in the two-dimensional plan view installed and minimum thickness as verified by the Road Thickness Survey as required by Section 01050 – Field Engineering.
2. Payment: The unit price bid for this item will be full compensation for all labor, materials, tools, equipment, supervision required to furnish and install the ABC Paving as shown on the drawings and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 16: Sidewalk

1. Measurement: The quantity of Sidewalk which will be paid for under this item will be the actual number of square yards of Sidewalk as measured in the two-dimensional plan view installed and minimum thickness of 4-inches.
2. Payment: The unit price bid for this item will be full compensation for all labor, materials, tools, equipment, and supervision required to furnish and install the Sidewalk as shown on the drawings and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 17: Concrete Scale Ramps

1. Measurement: The quantity of Scale Ramps to be paid for under this time will be the actual number of complete Scale Ramps installed as shown on the Drawings and accepted by the ENGINEER.
2. Payment: The unit price for the Scale Ramp shall be full compensation for all labor, materials, tools, equipment, supervision to furnish and install the Scale Ramp as shown in the Drawings and specified herein, including but not limited to, excavation and backfill, subgrade preparations, aggregate, geotextile, compaction, surveying, testing and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 18: Concrete Scale Foundation/Washout Slab

1. Measurement: The quantity of Concrete Scale Foundation/Washout Slabs to be paid for under this time will be the actual number of complete Concrete Scale Foundation/Washout Slab installed as shown on the Drawings and per Manufacturer's approved foundation plan and as accepted by the ENGINEER.
2. Payment: The unit price for the Concrete Scale Foundation/Washout Slab shall be full compensation for all labor, materials, tools, equipment, supervision to furnish and install the Concrete Scale Foundation/Washout Slab as shown in the Drawings and specified herein, including but not limited to, excavation and backfill, subgrade preparations, aggregate, geotextile, compaction, reinforcement steel, surveying, testing and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form. Contractor shall provide all engineering, labor, materials, tools, equipment and incidentals required for the design and installation of the scales structural foundation system.

Item 19: Scales

1. Measurement: The quantity of Scales to be paid for under this time will be the actual number of complete Scales installed as shown on the Drawings and per Manufacturer's instructions and as accepted by the ENGINEER.
2. Payment: The unit price for this item will be full compensation required to furnish and install scales as shown on the Drawings and specified herein, including but not limited to: scales with concrete decking and rub rails, electrical conduit and all else incidental to the work for which payment is not provided under other items in the bid form. Contractor shall provide all engineering, labor, materials, tools, equipment and incidentals required for the design and installation of the scales.

Item 20: Stabilization

1. Measurement: The quantity of Stabilization which will be paid for under this item will be the actual number of square yards stabilized as measured in place by computing the two-dimensional plan area of the limits of the Stabilization performed.
2. Payment: The unit prices bid for this item will be full compensation for providing all labor, materials, tools, equipment, supervision required to perform all work required to successfully complete the stabilization of disturbed areas as shown on the Drawings and specified herein, and the establishment of an acceptable vegetation (mix of grasses) as inspected and approved by the ENGINEER.

Item 21: Bollards

1. Measurement: The quantity of Bollards to be paid for under this item will be the actual number of Bollards installed as shown on the Drawings and specified herein and accepted by the ENGINEER.
2. Payment: The unit price bid for this item will be full compensation for Bollards installed as shown on the Drawings and specified herein including but not limited to labor; materials; installation; site restoration; and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 22: Water Service

1. The lump sum price bid for this item will be full compensation for all labor, materials, tools, equipment, supervision and incidentals required to install the 1-inch Water Service in accordance with the City of Hickory Engineering Department Manual of Practice, including valves, valve boxes, water service tap, meter box, water service line, and other appurtenances for which payment is not provided under other items in the bid form.

Item 23: Sewer Service Septic System

1. The lump sum price bid for this item will be full compensation for all labor, materials, tools, equipment, supervision and incidentals required to permit and install the Sewer Service Septic System in accordance with the Catawba County Health Department Standards, including surveying, piping, septic tank, and drain field and other appurtenances for which payment is not provided under other items in the bid form.

Item 24: Chain Link Fence and Gates

1. Measurement: The quantity of Chain Link Fence and Gates to be paid for under these items will be the actual number of linear feet of Fence, including Gates, in place measured horizontally along the fence by Contractor's final survey.
2. Payment: The unit price bid for this item will be full compensation for all labor, materials, fence alignment, clearing as necessary to install the fencing, concrete foundation, tools, equipment, supervision, and incidentals to furnish and install the chain link fence as shown on the Drawings and specified herein.

Item 25: Pavement Striping

1. The lump sum price bid for this item will be full compensation for all labor, materials, tools, equipment, supervision and incidentals required to install pavement striping accordance with the NCDOT Standards, including surveying, surface preparation, and other appurtenances for which payment is not provided under other items in the bid form

Item 26: Concrete Walls/Foundations (Tire Pad)

1. The lump sum price for Concrete Walls/Foundations (Tire Pad) shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Concrete Walls/Foundations (Tire Pad) as shown in the Drawings S.1, S.2, and S.3 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 27: Concrete Slab (Tire Pad)

1. The lump sum price for Concrete Slab (Tire Pad) shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Concrete Slab (Tire Pad) as shown in the Drawings S1.1, S1.2, and S1.3 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 28: PEMB Canopy

1. The lump sum price for PEMB Canopy shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for engineering, furnishing and installing the PEMB Canopy as shown in the Drawings B1.1, B1.2, and B1.3 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 29: General Conditions-Building

1. The lump sum price for General Conditions-Building shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the General Conditions-Building as shown in the Drawings G101-AS104 and S101-S102 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 30: Concrete

1. The lump sum price for Concrete shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Concrete as shown in the Drawings G101-AS104 and S101-S102 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 31: Masonry

1. The lump sum price for Masonry shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Masonry as shown in the Drawings G101-AS104 and S101-S102 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 32: Steel Carpentry

1. The lump sum price for Steel Carpentry shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Steel Carpentry as shown in the Drawings G101-AS104 and S101-S102 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 33: Moisture & Thermal Protection

1. The lump sum price for Moisture & Thermal Protection shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Moisture & Thermal Protection as shown in the Drawings G101-AS104 and S101-S102 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 34: Door, Windows, & Glass

1. The lump sum price for Doors, Windows, & Glass shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Doors, Windows, & Glass as shown in the Drawings G101-AS104 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 35: Finishes

1. The lump sum price for Finishes shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Finishes as shown in the Drawings G101-AS104 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 36: Specialties

1. The lump sum price for Specialties shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Specialties as shown in the Drawings G101-AS104 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 37: Plumbing

1. The lump sum price for Plumbing shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Plumbing as shown in the Drawings P001-P101 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 38: Mechanical

1. The lump sum price for Plumbing shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Plumbing as shown in the Drawings M001 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 39: Electrical

1. The lump sum price for Electrical shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Electrical as shown in the Drawings E101-

E201 and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

Item 40: Miscellaneous Work & Cleanup

1. The lump sum price for Miscellaneous Work & Cleanup shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required to perform work described in Section 02901 and as shown on the Drawings, and any other work not specifically included for payment under any other item but obviously necessary to complete the Contract.

~~Item 41: Landscape Buffer DELETED IN ADDENDUM 3~~

- ~~1. The lump sum price for Landscape Buffer shall be full compensation for all labor, materials, tools, equipment, supervision and incidentals required for furnishing and installing the Landscape Buffer as shown in the Drawings and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.~~

Item 41: Check Dam

1. Measurement: The quantity of Check Dams to be paid for under this item will be the actual number of Check Dams installed as shown on the Drawings and specified herein and accepted by the ENGINEER.
2. Payment: The unit price bid for this item will be full compensation for Check Dams installed as shown on the Drawings and specified herein including but not limited to labor; materials; installation; site restoration; and all other work required or incidental to the satisfactory completion of all work under this item for which payment is not provided under other items in the bid form.

END OF SECTION